

Vernon, Victoria; Zimmermann, Klaus F.

Working Paper

Walls and Fences: A Journey Through History and Economics

GLO Discussion Paper, No. 330 [pre.]

Provided in Cooperation with:

Global Labor Organization (GLO)

Suggested Citation: Vernon, Victoria; Zimmermann, Klaus F. (2020) : Walls and Fences: A Journey Through History and Economics, GLO Discussion Paper, No. 330 [pre.], Global Labor Organization (GLO), Essen

This Version is available at:

<https://hdl.handle.net/10419/222468>

Standard-Nutzungsbedingungen:

Die Dokumente auf EconStor dürfen zu eigenen wissenschaftlichen Zwecken und zum Privatgebrauch gespeichert und kopiert werden.

Sie dürfen die Dokumente nicht für öffentliche oder kommerzielle Zwecke vervielfältigen, öffentlich ausstellen, öffentlich zugänglich machen, vertreiben oder anderweitig nutzen.

Sofern die Verfasser die Dokumente unter Open-Content-Lizenzen (insbesondere CC-Lizenzen) zur Verfügung gestellt haben sollten, gelten abweichend von diesen Nutzungsbedingungen die in der dort genannten Lizenz gewährten Nutzungsrechte.

Terms of use:

Documents in EconStor may be saved and copied for your personal and scholarly purposes.

You are not to copy documents for public or commercial purposes, to exhibit the documents publicly, to make them publicly available on the internet, or to distribute or otherwise use the documents in public.

If the documents have been made available under an Open Content Licence (especially Creative Commons Licences), you may exercise further usage rights as specified in the indicated licence.

Walls and Fences: A Journey Through History and Economics*

Victoria Vernon

State University of New York and GLO; victoria.vernon@esc.edu

Klaus F. Zimmermann

UNU-MERIT, CEPR and GLO; klaus.f.zimmermann@gmail.com

Contribution to: Kourtit, K., Newbold, B., Nijkamp, P. and Partridge, M., The Economic Geography of Cross-Border Migration, Springer, Heidelberg et al.

Pre-publication Draft July 2020

Abstract

Throughout history, border walls and fences have been built for defense, to claim land, to signal power, and to control migration. The costs of fortifications are large while the benefits are questionable. The recent trend of building walls and fences signals a paradox: In spite of the anti-immigration rhetoric of policymakers, there is little evidence that walls are effective in reducing terrorism, migration, and smuggling. Economic research suggests large benefits to open border policies in the face of increasing global migration pressures. Less restrictive migration policies should be accompanied by institutional changes aimed at increasing growth, improving security and reducing income inequality in poorer countries.

JEL: F22, F66, H56, J61, N4

Keywords: Walls, fences, defense, security, international migration, mobility

* We thank K. Bruce Newbold and two anonymous reviewers for many helpful comments and suggestions on an earlier draft.

1. Introduction

Since the dawn of time, people have moved across land and ocean in search of a better life. When humans first left Africa to settle across the globe, they were motivated by their need for food, space and resources. Early large-scale migrations were people fleeing wars, famine and disease. Warriors and settlers from strong empires moved across continents to conquer weaker neighbors. Cross-border economic migration gained momentum in the 20th century, fueled by rising per capita incomes in poorer countries, booming international business, strengthened personal ties with people in foreign countries, and cost-cutting advances in transportation. Voluntary and peaceful labor mobility has been beneficial for migrants, whose labor is more productive in richer economies; for businesses in search of qualified workers; for the natives of host countries, whose assets gained value; and for migrants' families back home who receive transfers (Constant and Zimmermann, 2013; Zimmermann, 2014b; Blau and Mackie, 2016).

Foreign-born people now account for 28% of the total population of Australia, 23% of Israel, 20% of Canada, 13% of the US, 13% of Germany, and 12% of the UK¹. Yet even at its highest level ever, international migration is surprisingly uncommon: only about 3% of the world population lives outside of their country of birth². In the last decade, regional conflicts in the Middle East, rising inequality and poverty in Africa, violence in South America, and natural disasters in various parts of the world have sent a flow of refugees to Europe and the US. Between 2015-17, over 1.5 million refugees arrived to Europe by sea.³ This is a small fraction of 21.5 million people displaced by climate-related catastrophes between 2008-2015 (Miller, 2017).

Gallup estimates that 14% of world adults, 710 million people, would migrate permanently if they could, and even more would move temporarily.⁴ More than 40% of respondents from very poor countries and countries with armed conflicts are potential migrants. In Africa alone, working age population is projected to rise by about 1 billion in 2055, increasing the pressure at the gates to Europe and China, two areas where population is predicted to decline substantially (Bruni, 2019). The flow of refugees is likely to continue. According to the World Bank, water scarcity, crop failure and rising sea levels, will displace as many as 143 million people in Sub-Saharan Africa, South Asia, and Latin America by 2050 (Rigaud et al. 2018).

Faced with unprecedented inflows of immigrants, developed countries have a choice of policies to allow or restrict migration. Governments of richer nations have responded by

¹ The Organization for Economic Cooperation and Development <https://data.oecd.org/migration/foreign-born-population.htm>

² United Nations Population Fund <http://www.unfpa.org/migration>

³ The UN Refugee Agency <https://data2.unhcr.org/en/situations/mediterranean>

⁴ <http://news.gallup.com/poll/211883/number-potential-migrants-worldwide-tops-700-million.aspx>

erecting walls and fences, investing in border protection and adopting policies to restrict undocumented migration.

In this chapter, we examine the global phenomenon of building walls, fences, and other man-made physical barriers between nations. We offer a historical perspective on why border barriers existed in the past, and how the rationale for building walls has changed. We discuss the costs and benefits of walls and fences, and review literature on alternative policies, including the open border policy. Section 2 surveys the history of walls and fences. Section 3 discusses their rationale. Section 4 deals with the economics of open borders. And section 5 concludes.

2. A history of walls and fences

2.1 Ancient and medieval walls

Humans on all continents have been building walls for millennia. The main motive for their early construction was to defend city-states against armies of unwelcome nomadic neighbors. A large physical obstacle also served as a signal of political power, wealth and strength, intended to deter future threats, a claim to land, and a way to define who belonged inside and who stayed out. The scale of walls has differed greatly throughout history, ranging from simple barriers between cities to massive fortifications between kingdoms.

One of the oldest known city, Jericho in modern day Palestine, was walled as early as 8000 BC (Encyclopedia Britannica, 2019). The 600-meter long stone wall was built and improved over several hundred years. The wall had a tower and a long ditch, and was likely intended as protection against floods and raiders. The construction project required enormous amount of physical labor – excavating the ditch, cutting through solid rock for materials, and hauling the stone to assemble the wall itself. Economists today may wonder how our ancestors planned, organized and managed such a sophisticated project with so little training in engineering. This was a time when humans were barely transitioning from hunters to farmers, did not yet use domesticated animals, and would not invent metal tools or the wheel for thousands of years. It is not clear what kind of manpower was used - communal labor, hired workers, or early slaves - or what type of surplus of an essential tradable resource the population of Jericho produced through mining or agricultural production to generate enough wealth to finance the wall.

As ancient cities grew all over the world, so did the walls. In 3000 BC, a 9 km wall surrounded the largest city in the world: the Sumerian city of Uruk in modern Iraq, with a population of 80,000 residents (Dumper, 2007). Around 2030 BC, ancient Sumerians constructed a massive 160 km fortified barrier across its territory to keep out the Amorite nomadic tribes. It succeeded in fending

off enemies for a few years, until the invaders either broke through the wall or simply walked around it to destroy Sumerian cities (Spring, 2015).

Ancient Greeks built a number of walls, including the siege-proof long walls of Athens around 460 BC. The fortifications, extending from the city to its harbor, protected Athens during one war with Sparta, but the city surrendered after its navy was defeated at sea (Conwell, 2008).

Around 83-260 AD, the Roman Empire reinforced its borders with a variety of wall-and-ditch structures made of turf and stone, known as limes. Limes were intended to keep barbarian tribes out of the Roman Empire, and were also used as customs checkpoints for the movement of goods and people. Among the best known limes are the 118 km Hadrian's Wall, and the 60 km Antonine Wall in Scotland, a 750 km wall in North Africa, and 568 km Limes Germanicus in Germany. The Roman Empire invested heavily in its military, and for a while its military conquests supplied a steady supply of slave labor to service the walls. Over time, expansion slowed down, and pressure from neighboring barbarians increased. Overspending on the military and walls led to a financial crisis and a host of negative effects - oppressive taxation and inflation, widespread tax evasion, and a widening gap between the rich and the poor, foreshadowing its eventual collapse. Roman Limes made for a good defense from disorganized robbers from Britain to the Arabian Peninsula, yet they did not protect the empire against the better-organized barbarian armies of Vandals, Alans and Goths (Jones, 1964).

Around 460-512 AD, the Byzantines built the 56 km Anastasian Wall near Constantinople, a stone and turf system of fortifications with towers, forts and ditches. For over a century it helped protect the empire from invasions from the west, but two hundred years later, the wall was no longer manned due to decreased threats and the high cost of troops (Williams and Friell, 1998).

In 430- 570 AD, the Sasanid Empire, located in modern-day Iran, invested in several large-scale public defense projects to fortify its borders in response to territorial disputes with nomadic neighbors. The most impressive part of the project was the 200 km Gorgan Wall, the world's largest defensive structure at the time and a masterpiece of ancient engineering, made out of uniformly shaped mud bricks, featuring 38 forts, a well-engineered network of canals that acted as both a water supply system and a defensive moat, and a garrison of at least 20,000 troops. This effective border defense system is thought to have contributed to the empire's longevity for the next 200 years, but later it was abandoned as the empire's prosperity came to an end and its maintenance became unaffordable (Chaichian, 2013).

Between 430-800 AD, Anglo-Saxon kings built and maintained Offa's Dyke, a 240 km long ditch and piled soil structure. It was intended to demarcate the border between England and Wales, as well as defend against invaders. The Danish kings built and reinforced Danevirke, a 30 km long

defensive structure between 650-968 AD. It was last fortified before 1180, and then abandoned 150 years later (Pulsiano and Wolf, 1993).

Construction of the Great Wall of China began before 220 BC and continued until the 17th century, the total distance reaching 21,196 km. Its original purpose was to separate the civilized Chinese farming heartland from nomadic barbarians to the north, and to claim the disputed territory.⁵ Over time the wall became a tool to control trade, prevent smuggling, and serve as entry portal with customs checkpoint. Millions of conscripted peasants lost lives building the wall in harsh climate on steep hillsides due to inadequate transportation, inhumane living conditions, and insufficient food. Total annual expenditure on the wall in 1576 was estimated to cost three-quarters of the annual emperor's budget. Maintaining and garrisoning the wall was financed by higher taxes and revenues from government monopolies on selling salt and iron, at the expense of other social projects (Lovell, 2006). Early unconnected fortifications were not real obstacles against nomads. In later centuries, the wall did provide some protection, but not against the organized army of Genghis Khan in the 13th C. The wall did not protect against 19th and 20th C barbarians arriving by sea: Europeans, Americans, and Japanese (Waldron, 1989; Lovell, 2006; Jones, 2016a). Throughout Chinese history, weaker emperors made investment into the expensive wall as a policy of last resort when all other options - diplomacy, bribery, trade, tribute, or punitive military expeditions - had failed. In contrast, expansionist dynasties -Tang and early Ming- refused to repair the "wall of shame" of their military superiority (Langerbein, 2009). The wall did not prevent trade and cultural exchange: steppe nomads came to the early wall to trade horses and leather for pottery and clothing; Chinese rulers learned nomad's fighting techniques and integrated nomads as leaders of their own armies. Even though the protective function of the imperial wall was long obsolete in the 20th C, the government of communist China kept investing into the wall as it became a symbol of national identity, a monument to the military superiority of China, a poetic inspiration, and a lucrative tourist attraction.

Virtually all cities in Northern China had defensive walls from as early as 2000 BC. Larger cities with more economic activity had longer walls; frontier cities subject to a higher probability of attack had stronger walls. The protective function of the walls may have contributed to a perceived sense of security and attracted more people and commerce to the walled cities: even today these cities have larger population and employment densities (Ioannides and Zhang, 2017; Du and Zhang, 2018).

In Nigeria, a number of fortifications were built over several centuries from around year 800. Benin-city was possibly the largest urban planning project in the world at the time, a web of walls

⁵ Climate change has been identified as a major source of the nomadic invasions against the agriculturalists in mid-to-late imperial China (Pei et al., 2019).

with a total length of 16,000 km that enclosed an entire kingdom made of hundreds of interlocked cities and villages (The Guardian, 2016). Benin walls were destroyed by the Europeans in 1897. The other massive wall in the area, Sungbo Eredo, was a 160 km wall and ditch earthworks financed by a rich queen around year 1000, intended for defense, unification and as a shrine for spirit worshipping (Onishi, 1999).

In Mexico, a small Mayan city of Tulum was surrounded on three sides by a 740 m long wall around year 1200, for defense against larger city-states (Bley, 2011). In 1281, Japan built a 20 km stonewall Genko Borui against Mongol invasion, and it is said to have contributed to the defeat of the invaders (Vallet, 2016).

Between 1500-1800, the Russian empire fortified its southern borders with barricades of felled trees with ditches and earth mounds, palisades, watch towers and forts, moving the barriers south as the empire expanded. These fortifications protected against Tatars and other nomads who were active participants in the slave market, kidnapping thousands of Eurasians per year and selling them into slavery to the Ottoman Empire. They also prevented domestic runaway serfs from fleeing, and demarcated new land for peasant farmers (Kollmann, 2017).

Plagued with chronic raids and territorial disputes, settled agricultural tribes sought to protect themselves against outside threats to survival by asserting control over land and strategic routes. Walls were expensive to build and even costlier to maintain. Early construction materials - wood and mud bricks –would be eroded by weather, leveled by earthquakes, or ruined by invaders. Despite costing much in resources, wealth and manpower, ancient walls were only partially successful in achieving their intended goals. These defenses appeared to have worked for the lifetimes of their builders, sometimes for several subsequent generations, but ultimately lost their value (Spring, 2015). It is unclear whether the gain of security provided by walls was worth the opportunity cost of their construction, whether the damage inflicted by barbarians could outweigh the financial burden of the projects.

It is tempting to speculate how the building a wall relates to the lifecycle of a city-state or an empire. Do expanding, flourishing, or declining powers build defensive barriers? In pre-modern history, the pattern suggests that richer rulers whose power was on the decline were more eager to build a physical defense system. Excessive spending on the walls may have in turn weakened empires and expedited their collapse.

2.2 Modern walls

Between the late medieval times and early-20th C, empires rose and fell, national borders moved numerous times, finally settling on what later became political borders of modern nations. This period in history is characterized by declining violence in Europe: rates of homicide from violence and wars in European countries decreased 10-50 times during that time (Pinker, 2011). Pinker (2011) attributes the trend to the spread of the power of centralized authority with monopoly on the legitimacy of violence, adoption of law and order, the advent of diplomacy, development of trade partnerships, advances in transportation, the rise of literacy, increased life expectancy, adoption of the values of tolerance and human rights, aversion to violence and cruelty. Recognition of sovereignty over a territory among states became more common after the 1600s, in part due to advances in cartography that allowed better records of border lines (Jones, 2016). Consequently, the need for defense walls declined and fewer new defense barriers were built during that time.

While construction of physical barriers was on the decline, new legal border barriers emerged. Their purpose was no longer defense, but rather control over the movements of civilians. Early steps towards a modern passport system appeared in 14th C England, 16th C Germany, 17th C France and 18th C Russia with the introduction of migration permits (Torpey, 2000). Throughout 14-18th C population growth in Europe was slow, people were seen as wealth and a valuable asset for extraction of military service, taxes and labor, thus governments sought to restrict outbound migration. At various times European monarchies introduced restrictions on emigration of skilled labor, such as artisans (1534, England), ship builders, sailors and fishermen (1669, France). Prussia restricted all emigration without permission in 1686. China had severe punishments, even death, for anyone going abroad in the 16-18th C (Xu, 2005). The majority of European settlers who colonized the United States were 'illegal' migrants who bypassed emigration restrictions. Spain, Russia, England, Holland, and the Ottoman Empire, among other countries, welcomed immigrants and refugees with tax breaks and other incentives (Dowty, 1987).

Most Western countries adopted passports and visas after WWI. Travel documents, ID cards, registration and censuses, were early forms of state surveillance and control over citizens' identities and their whereabouts. By allowing or depriving people of the freedom to move, states could efficiently conduct law enforcement, prevent potential anti-government insurgencies, target national security operations, distribute incentives and punishments, prevent brain drain, administer claims to assets, supervise population growth and composition (Torpey, 2000).

Leading up to WWII, Europe experienced a revival of defense fortifications. Finland constructed two lines of fortified defense on the Soviet border in 1920–1940, the Mannerheim Line

with fallen trees and boulders, and the Salpa Line with 350,000 stones weighing 3 tons each. Czechoslovakia 1935-38 built border fortifications with infantry blockhouses and antitank obstacles. Greece built the 155 km long Metaxas Line of 21 independent fortification complexes to protect from Bulgarian invasion in 1936-41. France 1929-38 constructed the Maginot Line, a 380 km long permanent system of fortifications with concrete bunkers, tunnels, tank obstacles, artillery casemates, machine gun posts along the German and Italian borders. Sweden built the 500 km Skåne Line on its borders with barbed wire and concrete bunkers along the shore, armed with machine guns and cannons. Mussolini's Italy 1930-42 built the Alpine Wall, a system of defensive fortifications along the 1851 km of its northern frontier facing France, Switzerland, Austria and Yugoslavia. Nazi Germany built the Atlantic Wall equipped with coastal guns, batteries, mortars, artillery, and thousands of stationed troops along the coast of continental Europe and Scandinavia in 1942-44 against an anticipated Allied invasion from the United Kingdom (Kaufmann and Donnell, 2004). None of these wartime fortifications could stop attacks by air, and some did not even deter the enemy armies arriving by land and sea. When the Allies eventually invaded the Normandy beaches, most of the Atlantic Wall defenses were stormed within hours. In the case of the Maginot Line, Nazis avoided it while invading France using an alternative route through Belgium.

After WWII, the United Nations was formed and countries recognized each other's political borders and territorial integrity. The triumph of diplomacy and peaceful coexistence could render the border walls and fences obsolete. However regional conflicts persisted, and security walls were a frequent solution.

France built an electric fence with minefields, the Morice Line, before the Algerian War of 1957, to prevent the rebel guerrillas from entering Algeria from Tunisia and Morocco. Israel built a 150 km defense system known as the Bar Lev Line, a massive sand wall supported by a concrete wall, along Suez Canal during the 1967 Six-Day War with Egypt, Jordan and Syria. Guantanamo /Cuba, and China/Hong Kong fortified their mutual borders with 30 km walls in the early 1960s. Oman built a 50 km mined Hornbeam line against guerrilla insurgents in 1973 (Peterson, 2008). Cyprus was divided by a UN buffer zone after Turkey took over Northern Cyprus in 1974, and Northern Cyprus built a 300 km concrete wall. Morocco built a 2,700 km sand 'berm' with trenches, barbed wire and landmines against Western Sahara in 1987 to claim disputed territory. North and South Korea built a 243 km heavily fortified demilitarized zone in the late 1970s.

During the Cold War of 1945-91, the Soviet Union and its allies put up the 'iron curtain', a set of self-imposed physical, legal and informational barriers between themselves and the West intended to prevent trade with the West and to stop emigration of citizens to the West, in order to

protect the emerging fragile new communist society based on work, cooperation, and egalitarianism from western capitalism based on individualism, competition, and hierarchy. It also included militarized borders with the West: a 240 km electric fence between Hungary and Austria, and the Berlin Wall.

Berlin Wall, built by East Germany in 1961, was a complex 150 km long system with sensors, a fence, barbed wire obstacles, dog-runs, an anti-tank ditch and obstacles, an access road for guards and vehicles, an alley of lights, 186 guard towers, a control strip of raked sand, followed by the main exterior wall with 25 border crossings. The wall employed 12,000 elite patrol soldiers and 1,000 dogs; troops were equipped with 567 armored personnel carriers, 156 heavy engineering vehicles, 2,295 other vehicles, 48 anti-tank guns, 48 grenade launchers, and 114 flame throwers. Despite the high tech engineering of the wall, tens of thousands of East Berliners managed to escape by climbing over the wall, digging under, and hiding in secret compartment of cars; 75,000 people received prison sentences for attempting to flee, and 140 lost lives. Operating much like a prison wall, the Berlin Wall blocked emigration of skilled labor without which East Germany would arguably not be able to survive. It extended the life of the regime by at most 28 years till 1989, and when it finally proved to be an economic failure, the wall collapsed along with the ideology that supported it (Rottman, 2012).

Fences erected by communist regimes were the only physical barriers in history intended to restrict out-migration. At least 5 were demolished at the end of the Cold War (Berlin Wall, Hungary-Austria, Czechoslovakia-West Germany, USSR-Finland, USSR-Norway), only the barrier between the Koreas remained. In contrast, the rest of the world was about to see a wave of walls against inbound migrants.

South Africa put up a lethal electrified fence on its border with poorer neighbors Mozambique and Zimbabwe in 1986. The fence was responsible for hundreds of refugee deaths in the first 3 years of its existence as migrants who tried to cross the fence got electrocuted, while those who tried to bypass the fence by going through a national park got eaten by lions. Yet most illegal migrants managed to cross the fence (New Scientist, 1990).

The decade of 1990s was marked by giant strides of the developed world towards unification, as evidenced by the adoption of NAFTA and common borders in the EU. But it was also the decade of fast population growth and rising inequality, the emergence of new regional conflicts, and the expansion of trade in drugs, weapons and human trafficking.

Between 1990-2001, six security walls were built against potential terrorists (here and elsewhere the first country is the builder): Israel/Gaza, Kuwait/Iraq, India/Bangladesh, Uzbekistan/Afghanistan, Uzbekistan/Kyrgyzstan, Turkmenistan/Uzbekistan. In addition, two

countries built migration walls: US/Mexico, and the Spanish enclaves of Ceuta and Melilla in Morocco. Smuggling of drugs, weapons and other controlled goods were secondary reasons for several of these fences. Although not explicitly stated, claims to land may be additional reasons to erect walls in case of Israel, India and Central Asian countries, given their history of territorial disputes.

2.3 21st C Walls

Concerns over terrorism magnified after the terrorist attacks of 9-11-2001 in the US. Other countries including Israel, UK, Spain, Indonesia, Russia, Bangladesh, Pakistan and India, were also attacked by terrorist organizations. Between 2002-2010, fifteen new security walls and fences were added to the map around Middle East, when ISIS insurgency began to threaten stability in the region. Israel built security fences separating it from the West Bank and Egypt. Egypt built an over-and under-ground wall with Gaza. Saudi Arabia built an 885 km security wall with Iraq and fences with UAE, Oman, Qatar, Jordan and Yemen. UAE erected fences along its borders with Saudi Arabia and Oman (migration, smuggling, security). Jordan built walls with Syria and Iraq. Iran walled off Iraq, Afghanistan and Pakistan (security, smuggling). Israel Defense Forces claim that the Israeli-Egypt fence was effective in reducing the flow of illegal migrants from Africa.⁶

Outside Middle East, eight new fences were constructed: between Brunei/Malaysia (smuggling, migration), Myanmar/Bangladesh (security), Lithuania/Belarus (smuggling), Kazakhstan/Uzbekistan (smuggling), and Kazakhstan/Kyrgyzstan (smuggling). Russia built a barbed wire barricade on the border with Georgia (conflict). In Africa, Botswana put up a fence against Zimbabwe in response to a flood of refugee migrants who were accused of taking jobs, committing crimes and spreading HIV (Kopinski and Polus, 2012).

In response to massive migration of Middle Eastern and North African refugees to the EU between 2011-2018, seven migration fences went up in Europe. Macedonia built a fence with Greece. Greece and Bulgaria have erected barbed wire fences on the border with Turkey. Hungary built a 175 km fence on the border with Serbia and a 350 km fence on the border with Croatia. Slovakia put a fence with Croatia, Austria with Slovenia. The UK financed a 13-foot-high barrier in the French port city of Calais, aimed at preventing refugees and migrants from entering Britain.

Middle East and North Africa added nine more security fences, fully or partially built: Oman/Yemen, Turkmenistan/Afghanistan, Pakistan/Afghanistan. Turkey/ Syria, Turkey/ Iran, Israel /Jordan, Israel/ Syria, Israel/Lebanon, Tunisia/Libya, and Algeria/Morocco.

⁶ Financial Times <https://www.ft.com/content/ccf4b532-3935-11e6-9a05-82a9b15a8ee7>

Regional conflicts and land disputes resulted in seven additional fences in Eastern Europe and Asia: Azerbaijan/Armenia, Ukraine/ Russia, Estonia, Latvia, Lithuania built barriers with the Russian territory of Kaliningrad, Kyrgyzstan /Kazakhstan, Kyrgyzstan/ Uzbekistan, and China/ North Korea.

Several countries have announced future construction of fences: Estonia/Russia, Latvia/Belarus, Poland/Belarus, Poland/Ukraine, Hungary/Romania, Turkey/Iraq, India/Bhutan, Malaysia/Brunei, Malaysia/Indonesia, Russia (Crimea)/Ukraine, and Algeria/Libya. These appear to be mostly motivated by smuggling, territorial claim, and animal disease control. Latin America is free of border barriers except for those erected by the US between Guantanamo and Cuba.


In addition to border walls between countries, there are separation walls within countries intended to reduce violence. One example is a wall in Baghdad built in 2007 by the US to separate a Sunni district. Another example is a series of forty "peace walls" in Belfast, Northern Ireland, constructed in the 1970s to separate Catholic and Protestant communities.

Modern borders differ greatly in their level of complexity and enforcement. Among the most serious borders is Kuwait/Iraq, made of electrified fencing and razor wire, braced by a 4.6 m-wide and 4.6 m-deep trench, complete with a 3.0 m-high dirt berm, and guarded by hundreds of soldiers, several patrol boats, and helicopters. Saudi Arabia/Iraq wall is equipped with ultraviolet night-vision cameras, buried sensor cables, thousands of miles of barbed wire, 50 radars, 78 monitoring towers, eight command centers, ten mobile surveillance vehicles, 38 night vision camera-equipped gates, 32 rapid-response centers, and three rapid intervention squads, all linked by a fiber-optic communications network. Some of the equipment used at the borders can detect a person 19 km away and a vehicle at 39 km⁷. Among relatively porous borders are fences between Malaysia/Thailand, and India/Bangladesh. Both are lightly patrolled and monitored, and thus not effective deterrents for migrants and smugglers who often use fake documents and bribes to cross between the two countries.

We estimate that at least 67 international borders are fortified to various degrees with man-made barriers as of 2018, and there are plans to build 10 more in the next few years. These borders are precisely documented in the Appendix Table: Modern Walls and Fences and illustrated in Fig. 1: Border Walls and Fences 1970-2020 below.

⁷ Gulf News Jan 22, 2015 <http://gulfnews.com/news/gulf/saudi-arabia/saudi-arabia-building-hi-tech-border-fence-1.1445112>

Figure 1. Border Walls and Fences 1970-2020.



Note: The graph presents the authors' count of all walls and fences in the world, including partially constructed (Estonia-Russia fence) and planned through 2020. Our estimates are overall similar to those in Vallet (2014), Jones (2016) and Carter and Poast (2017), although our estimates are more conservative. Vallet, Barry and Guillarmou (quoted in Jones, 2016) suggest an estimate of 69 fences in 2016 while our count is 63. We include only walls and fences on international borders (this excludes the Wall of Baghdad, the Walls of Peace in Belfast, and the Great Wall of China), the existence of which we could verify. For example, we are not sure if there is a fence on the border of Russia with China, Mongolia, and North Korea. There is probably at least partial fencing, but in the absence of information we did not count them. As construction start dates differ between sources, we used the most commonly reported dates. The Appendix Table 1 lists all walls and fences included into our calculations. Rosière and Jones (2012) estimate that by 2012 more than 13 percent of the world's borders were marked with a barrier of some kind.

2.4 US-Mexican wall

The US-Mexico wall is an example of a border barrier with several official motives behind it: stop illegal migration, fight drug and human smuggling, and prevent drug-related violence (Andreas, 2000; Dear, 2013). The first piece of the wall, the 22 km San Diego fence, was built in 1990-93. Since 2006, a total of 1,000 km of steel and concrete were added in various parts of this 3,200 km border. About one-third of the border consists of natural barriers such as desert stretches and the Rio Grande. In between the walls, there is "virtual fencing" composed of sensors, surveillance cameras, and other detection technology. Since 9/11, the US side of the border has been further militarized, and the border patrol budget increased 20 times. There are plans to add another 1,000 km of the wall in the near future with the total cost up to \$25 billion, including labor but not including the cost of land

acquisition from current owners. Once constructed, the government will need to invest a few billion a year in wall maintenance, repairs, guards, and support infrastructure (Economist, 2016).

The number of undocumented immigrants in the US increased between 1986-2008 from about 3 to 12 million people, or 7% of the US population. In the 1960s, 70 million Mexicans crossed the border, but 85% returned home. Increased border enforcement made circular migration more costly and risky, forcing undocumented Mexican migrants to settle permanently in the US (Zimmermann, 2014, Massey et al., 2016).

The US-Mexican wall does not deter drug smuggling. Most illicit drugs are delivered into the US in vehicles with secret compartments and difficult-to-inspect shipping cargo using legal checkpoints. Drugs are also conveyed through elaborate systems of tunnels under the wall. Between 1990 and 2016, 224 tunnels were discovered, some with air vents, rails and electric lights (US DEA 2016).

Stricter border enforcement in the US raised the cost of human smuggling by pushing it farther into the desert into the hands of large drug cartels. Coyotes used to work independently or in small groups. Now they work for one of the four narco cartels, paying the cartels a huge cut of the profits. If migrants try to cross the border without paying, they risk getting beaten or murdered. The average price is upward of \$4,000 in 2017 dollars (US DHS, 2017). Smugglers are more often armed and violent, and conflicts between them and border enforcement agents resemble a war. Migrants are sometimes left to die in the desert: there have been 4,500 migrant deaths along the U.S.-Mexico border between 2006-17 (US Customs and Border Protection, 2017).

Similar dynamics is observed in Europe. The Greek fence has forced migrants to pursue more dangerous and expensive alternative routes. Trips on the Eastern Mediterranean route from Turkey's Western Coast to Greece now cost over €1,000 (Stamouli, 2016). Between 2014-17, over 11,000 migrants died or went missing in the Mediterranean at sea⁸.

The number of people detained without papers on the US-Mexico border has dropped markedly in 2017 to the lowest number since 2000 (US DHS, 2017). Illegal immigration is on the decline because of demographics: Mexico's birth rate has plummeted during the last 40 years from 6.1 children per woman in 1975 to 2.2 in 2005, which is not very different from 1.8 births per women in the US.⁹

⁸ Migration Data Portal <https://migrationdataportal.org>

⁹ World Bank Open Data <https://data.worldbank.org>

3. Making sense out of walls

Consider the construction of a border barrier from a costs-and-benefits perspective. Costs include electric lighting, roads, security equipment and guards. A physical wall requires masonry foundations, steel and concrete, which is relatively expensive, while barbed wire fences are cheaper. Resources spent on walls and border enforcement come with opportunity costs - they could have been directed to alternative uses, such as building better schools and improving cities.

Should a security wall be built to prevent the infiltration of terrorists? Terrorism is costly for an economy as it leads to loss of life and destabilizes investment in productive assets. For example, terrorist attacks committed by the Somali terrorist group Al Shabaab have had a large negative impact on Kenya's economy in recent years.¹⁰ A security fence may be justified in this case, even though Kenya does not have one. The costs of a security fence can be weighed against the benefits of preventing an attack for a country that faces threats from terrorism. One should keep in mind that historically, walls have not been effective against military attacks (Jones, 2016). In recent times, most terrorist attacks in the US and Europe have been committed by legal residents 'from within'. The strongest walls could not have stopped 9/11. Planes and missiles can fly over walls, tanks can smash them, and biological weapons, drones and cyberattacks bypass walls entirely. The security effectiveness of borders does not depend on military spending, but rather is a function of institutional design that encourages local cross-border collaborative policing (Gavrilis, 2008).

Should a wall be built to prevent smuggling of illicit drugs and weapons? There is little evidence that walls are effective in the war on drugs. Even if they are, the cost of such barriers should be weighed against the results they achieve, given other law and policy options to regulate drugs and guns.

The main driving factor of undocumented migration – and therefore of walls - is inequality. Richer countries build walls against poor neighbors. Jones (2012) estimates that the average GDP of a country that built a barrier, from 2000 to 2011, was 5 times larger than the GDP of the target country. Similarly, Carter and Poast (2017) find statistical evidence that economic disparities have a significant impact on the presence of a physical wall using data on barriers constructed from 1800 to 2014. Therefore addressing the problem of poverty and inequality in the developing world is often suggested to be a way to reduce migration. However, this is only valid in the very long run.¹¹

¹⁰ The Conversation <https://theconversation.com/why-al-shabaab-targets-kenya-and-what-the-country-can-do-about-it-87371>

¹¹ Economic development and emigration from developing countries are found to be inverse U-shaped. Hence, rising income increases the possibilities for migration, but migration has also a positive impact on development back home. See for a review of the rich literature Clemens (2014) and specific articles like Haas (2010), Zimmermann (2017a, 2017b), and Dao et al. (2018).

Should a wall be built against illegal immigrants? The benefit of a migration wall may be high if uncontrolled migration imposes large costs on a society and if a wall provides sufficient protection against such inflows. For example, immigrants may commit crime, drain welfare resources, threaten national unity, and impose hardship on domestic workers. The cost effectiveness of building a wall should also be compared to the alternative options of regulating migrant's privileges with policies.

Certain groups and industries – potential voters who influence policymaking - benefit from the proliferation of walls and militarization of borders. For example, the growth in border barriers created a multi-billion-dollar security business for private armament and defense companies specializing in communications, surveillance, information technology and biometrics. Between 2002 and 2017, exports of Israeli companies specializing in high-tech border security increased 22% each year. Major international companies that have a large share in this market are American *Boeing*, Israeli *Elbit Systems*, Israeli *Magal Security Systems*, Spanish *Amper*, European *EADS Group* (Saddiki, 2017). Among other likely beneficiaries will be Cemex, a Mexican firm with around half the quarries close to the border, given that it is not economically feasible to transport cement across great distances. Then, there are companies like the US Golden State Fence Company, a firm that built a significant portion of the border wall in Southern California, and was charged millions of dollars in fines for having hundreds of undocumented workers on its payroll.¹² The list of groups that stand to benefit from the wall also includes the Department of Homeland Security that employs 240,000 people and has an annual budget of \$61 billion, including border enforcement, militarized police units, ammunition, detention centers, biometric IDs and surveillance (Miller 2017).

All types of border barriers reduce wellbeing of the population by restricting gains from cooperation, specialization and trade between neighbors. Allen et al. (2018) show that the US-Mexico border wall expansion between 2007-10 harmed Mexican workers and high-skilled U.S. workers, but benefited U.S. low-skilled workers, who achieved gains equivalent to an increase in per capita income of \$0.36. In contrast, a hypothetical policy of openness, which reduced trade costs between the United States and Mexico by 25%, would have resulted in both greater declines in Mexico to United States migration and substantial welfare gains for all workers.

The non-economic costs of walls include isolation, broken cultural ties, mistrust that can breed terrorism, damaged farmlands, and a threat to wildlife (Trouwborst et al., 2016). Political scientist Brown (2010) writes the following about Israeli and US-Mexico walls in the book 'Walled States': "Both intensify the criminality and violence they purport to repel, and hence, both generate the need for more fortifications and policing. Yet both are heralded for producing peace, order, and security.

¹² New York Times <http://www.nytimes.com/2006/12/15/us/15hiring.html>

Both confound barricades and borders, and both articulate a border on confiscated lands. Both walled democracies are justified as state necessity in protecting the people, both draw upon the xenophobia they also exacerbate and project, both suspend the law in the name of blockading outlaws and criminals, and both build a "suspended political solution" in concrete and barbed wire".

Popular justifications for restricting migration are not based on real evidence, but rather the examples of signaling behavior by governments. In the words of Jagdish Bhagwati who spoke of the India-Bangladesh fence construction in the 1980s, for a politician, building a fence is "the least disruptive way of doing nothing while appearing to do something." (quoted in Di Cintio, 2013).

4. Open or closed borders?

There is a lively debate in the economic literature around the potential consequences of allowing more migration. Kennan (2013, 2014) and Clemens (2011) argue that lifting the restrictions on immigration could produce large efficiency gains because the unskilled workers become more productive when they move from a low wage to a high wage country. As a result, incomes in less-developed countries could more than double and the world GDP would increase by 67-147%.

A large body of research has documented that increased cross-border labor mobility has beneficial effects for host countries and their residents. For example, the EU labor market has become more flexible and better able to absorb shocks after the EU eastern enlargement (Kahanec and Zimmermann, 2009a,b, 2016; Jauer et al., 2019) and this is attributed not only to migrants from the (new) member states but also to third-country nationals.

There is evidence that immigrants do not take jobs away or depress wages. Instead migrants help create jobs for natives, because their skills are most often complements rather than substitutes for the skills of native workers in the production of goods and services (Constant 2014; Peri 2014, Fogel and Peri, 2016). High-tech startups and established firms owned by foreign-born entrepreneurs have introduced more innovations than firms owned by US-born entrepreneurs (Brown, 2019).

Labor migrants tend to be economically successful taxpayers, and are less likely than natives to use welfare benefits (Giulietti and Wahba, 2013). In the EU, the generosity of unemployment benefit spending across EU countries in 1993-2003 had a negligible effect on the inflow of non-EU migrants (Giulietti, Guzi, Kahanec and Zimmermann, 2013). In the US, the overall cost of public benefits is substantially less for low-income non-citizen immigrants than for comparable native-born adults and children (Ku and Bruen, 2013).

It has been shown that higher share of foreign labor is associated with more equality in developed countries (Kahanec and Zimmermann, 2009b, 2014). Social tensions are smaller and

attitudes towards migrants are more open if immigrants are selected according to the needs of the labor markets (Bauer et al., 2000). The wellbeing of natives is shown to be higher in countries with more - and with more diverse - migrants (Akay et al., 2014; Akay et al., 2017).

Immigrants commit fewer offenses and less frequently end up in prison than the native population. For example, the number of illegal immigrants in the US tripled between 1990 and 2013, while the crime rate plummeted (Ewing et al., 2015). Data on migration flows between 145 countries between 1970-2000 shows that immigration does not cause terrorism; immigration leads to a decline in terrorist acts, largely because it fosters economic growth (Bove and Böhmelt, 2016).

Labor migration, particularly that of undocumented workers, is largely circular migration in the absence of travel barriers, because workers go back home to their families after temporary work episodes abroad (Zimmermann, 2014, Constant et al., 2013, Massey and Pren, 2012). Mobility restrictions, paradoxically, create more permanent migrants, because workers, unable to move freely to and from the host country, bring families with them. This scenario selects for migrants who may be less willing to assimilate, and the children of immigrants remain culturally diverse (Galli and Russo, 2019). When immigrant workers travel back and forth between their host and home countries, the home countries benefit from their skills, knowledge and perspective, as well as from investments into local businesses and money they spend at home. Remittances sent home by migrants contribute to the development of some of the world's poorest countries, accounting for over 30% of GDP in Kyrgyz Republic and Tajikistan, around 25% in Haiti and Yemen, and close to 20% in Moldova, Honduras and El Salvador¹³. In other words, immigrants send home 3-4 times more money than countries receive in development aid.

Given the evidence, open borders policies rather than walls would improve the world wellbeing. What are some of the drawbacks? Large inflows of migrants may be disruptive for the welfare system in the short-run, even if in the long-run the balance is restored. Host country natives may have legitimate concerns about preserving national identity and granting voting rights to the newcomers. Potential higher demand for housing, schooling, medical care, and the accompanying rise in property prices are also important short-run concerns.

In a world where wealth and opportunities are more equally distributed, a smaller number of individuals would be drawn by labor market needs or want to migrate to explore different cultures. More people would prefer to stay to be close to their extended families and friends and the home country culture. Unfortunately, simple solutions such as sending foreign aid to poor countries do not

¹³ World Bank Migration and Remittances Data 2018
<http://www.worldbank.org/en/topic/migrationremittancesdiasporaissues/brief/migration-remittances-data>

reduce emigration (Clemens and Postel, 2018).¹⁴ In fact, rising incomes in developing countries may have the opposite effect at least initially, it will increase mobility among people who need resources to move. Reducing migration from poor countries requires complex solutions to global poverty, inequality and conflicts. Long-term solutions to migration crisis should involve development of institutions in poor countries, including law and order, property rights, as well as investment in education, reduced corruption, and peaceful governance.

5. Conclusions: Politics vs Economic Evidence

Contemporary border fences are built for much the same set of reasons as ancient walls. We have defense walls against external threats of terrorism and infiltration by insurgents. There are walls that separate conflicting cultures and religions, walls that establish ownership of land, barriers that regulate trade, and fences that restrict migration of civilians. The attributes of walls have changed from earthwork, bricks and masonry to sophisticated structures that include concrete, razor wire, sensors, personnel, dogs, infrared equipment, patrol vehicles, drones, helicopters, planes and satellites. There are additional invisible walls made of legal and digital barriers to restrict movement of goods and people, and maritime systems to detect unauthorized boats.

Like ancient walls, modern ‘security walls’ are only partially successful in accomplishing their goals. No physical barrier can provide effective protection against homegrown terrorists and modern weapons. No fortification can stop migrants who arrive by air and sea. No wall will reduce the drug flow when most of it crosses the border through legal entry points. More than ever before, walls today are politically motivated, reflecting signaling behavior by governments who wish to appear tough on immigration, and serving the interests of defense industries that stand to benefit from the projects. Economic literature overwhelmingly suggests that policies of more open borders, with less restrictive migration and trade, benefit domestic citizens more than walls. Economic policies are also more effective than walls in dealing with illegal trade and trafficking, while diplomacy is more effective than walls in addressing security. Ignoring rational economic thinking over populist politics comes at a price, a loss in well-being.

¹⁴ See also footnote 10 and the literature cited there.

References

- Allen, Treb, Dobbin, Cauê de Castro and Morten, Melanie (2018), Border Walls, NBER Working Papers 25267, National Bureau of Economic Research, Inc.
- Alpaslan Akay, Constant, Amelie and Giulietti, Corrado (2014), The Impact of Immigration on the Well-Being of Natives, *Journal of Economic Behavior and Organization*, Vol. 103, pp. 72-92.
- Alpaslan Akay, Constant, Amelie, Giulietti, Corrado and Guzi, Martin (2017), Ethnic Diversity and Well-Being, *Journal of Population Economics*, Vol. 30, pp. 265-306.
- Andreas, Peter (2000), *Border Games: Policing the U.S.–Mexico Divide*. Ithaca, NY: Cornell University Press.
- Bauer, Thomas, Lofstrom, Magnus and Zimmermann, Klaus F. (2000), Immigration Policy, Assimilation of Immigrants, and Natives' Sentiments Towards Immigrants: Evidence from 12 OECD Countries, *Swedish Economic Policy Review*, Vol. 7, pp. 11-53.
- Blau, Francine D. and Mackie, Christopher (2016), (Eds.). *The Economic and Fiscal Consequences of Immigration*, A Report of the National Academies, Washington DC.
- Bley, Bonnie (2011), *The Ancient Maya and Their City of Tulum: Uncovering the Mysteries of an Ancient Civilization and Their City of Grandeur*, iUniverse.
- Bove, Vincenzo and Böhmelt, Tobias (2016), Does Immigration Induce Terrorism? *The Journal of Politics*, Vol. 78:2, pp. 572-588.
- Brown, David, Earl, John, Kim, Mee Jung and Lee, Kyung Min (2019), Immigrant Entrepreneurs and Innovation in the US High-Tech Sector. NBER Working Paper No. 25565, February.
- Brown, Wendy. (2010). *Walled States, Waning Sovereignty*. Zone Books, New York.
- Bruni, Michele (2019): *The World at the Crossroad. Demographic Polarization and Mass Migration. Global threat or global opportunity*, GLO Discussion Paper Series No. 301, Global Labor Organization (GLO).
- Carter, David B. and Poast, Paul. Why Do States Build Walls? (2017), Political Economy, Security, and Border Stability, *Journal of Conflict Resolution*, Vol. 61, Issue 2, pp. 239-270.
- Chaichian, Mohammad (2013), *Empires and Walls*, Brill.
- Clemens, Michael A. (2011), Economics and Emigration: Trillion-Dollar Bills on the Sidewalk? *Journal of Economic Perspectives*, Vol. 25:3, 83-106.
- Clemens, Michael A., Does Development Reduce Migration? (2014), in: Robert E.B. Lucas (Ed.), *International Handbook on Migration and Economic Development*, Edward Elgar, pp. 152-185.

- Clemens, Michael A., Postel, Hannah (2018). Deterring Emigration with Foreign Aid: An Overview of Evidence from Low-Income Countries. *Population and Development Review*, Vol 44, Issue 4, pp. 667-693. <https://doi.org/10.1111/padr.12184>
- Constant, Amelie F. (2014), Do Migrants Take the Jobs of Native Workers? *IZA World of Labor*: 10.
- Constant, Amelie F., Nottmeyer, Olga, and Zimmermann, Klaus F. (2013), The Economics of Circular Migration,” in: Constant, Amelie F., and K. F. Zimmermann, K. F. (eds). *International Handbook on the Economics of Migration*. Cheltenham, UK: Edward Elgar, 2013; pp. 55–74.
- Constant, A. F., & Zimmermann, K. F., (Eds.) (2013). *International handbook on the economics of migration*, Cheltenham, UK: Edward Elgar.
- Conwell, David, (2008). *Connecting a City to the Sea: The History of the Athenian Long Walls*. Brill, Academic Pub.
- Dao, Thus Hien, Frédéric Docquier, Chris Parsons, Giovanni Peri. (2018), Migration and Development: Dissecting the Anatomy of the Mobility Transition, *Journal of Development Economics*, Vol. 132: May, pp. 88-101.
- Dear, Michael (2013), *Why Walls Won't Work: Repairing the U.S.-Mexico Divide*. Oxford, UK: Oxford University Press.
- Di Cintio, Marcello (2013), *Walls: Travels Along the Barricades*, Union Books, 2013.
- Dowty, Alan (1987), *Closed Borders: The Contemporary Assault on Freedom of Movement*. Yale University Press.
- Du, Rui and Zhang, Junfu (2018), Walled Cities and Urban Density in China. Forthcoming: *Papers in Regional Science*. <https://doi.org/10.1111/pirs.12415>
- Dumper, Michael and Stanley, Bruce E., ed., (2007). *Cities of the Middle East and North Africa: A Historical Encyclopedia*, ABC-CLIO.
- Economist, July 26, 2016. The Economics of Donald Trump's Wall. <https://www.economist.com/graphic-detail/2016/07/26/the-economics-of-donald-trumps-wall>.
- Encyclopedia Britannica, Jericho <https://www.britannica.com/place/Jericho-West-Bank>. Accessed February 4, 2019.
- Ewing, Walter, Martínez, Daniel E. and Rumbaut, Rubén G. (2015), *The Criminalization of Immigration in the United States*. American Immigration Council. Special Report.

- Foged, Mette and Peri, Giovanni (2016), Immigrants' Effect on Native Workers: New Analysis on Longitudinal Data, *American Economic Journal: Applied Economics*, Vol. 8: 1- 34.
- Galli, Fausto and Russo, Giuseppe (2019), Immigration Restrictions and Second-generation Cultural Assimilation: Theory and Quasi-experimental Evidence, *Journal of Population Economics*, Vol. 32:1, pp. 23-51.
- Gavrilis, George (2008), *The Dynamics of Interstate Boundaries*. New York: Cambridge University Press.
- Giulietti, Corrado and Wahba, Jackline (2013), Welfare Migration, in: Constant, Amelie F. and Zimmermann, Klaus F. (Eds.), *International Handbook on the Economics of Migration*, Edward Elgar: Cheltenham, pp. 489-504.
- Giulietti, Corrado, Guzi, Martin, Kahanec, Martin and Zimmermann, Klaus F. (2013), Unemployment Benefits and Immigration: Evidence from the EU, *International Journal of Manpower*, Vol. 34:1, pp. 24-38.
- The Guardian, Benin City, the mighty medieval capital now lost without trace, March 18, 2016.
<https://www.theguardian.com/cities/2016/mar/18/story-of-cities-5-benin-city-edo-nigeria-mighty-medieval-capital-lost-without-trace>
- Haas, Hein de (2010), Migration Transitions. IMI Working Papers. International Migration Institute.
- Ioannides, Yannis, and Zhang, Junfu (2017), Walled Cities in Late Imperial China, *Journal of Urban Economics*, Vol. 97, pp. 71-88.
- Jauer, Julia, Liebig, Thomas, Martin, John P. and Puhani, Patrick A. (2019), Migration as an Adjustment Mechanism in the Crisis? A Comparison of Europe and the United States 2006 - 2016, *Journal of Population Economics*, Vol. 32:1, pp. 1-22.
- Jones, A.H.M. (1964). *The later Roman Empire 284-602. A social economic and administrative survey*, two volumes. Oxford: Blackwell.
- Jones, Reece (2012a), *Border Walls: Security and the War on Terror in the United States, India, and Israel*, Zed Books: London.
- Jones, Reece (2016), *Borders and Walls: Do Barriers Deter Unauthorized Migration?*, *Migration Information Source*, The Online Journal of the Migration Policy Institute,
<https://www.migrationpolicy.org/article/borders-and-walls-do-barriers-deter-unauthorized-migration>
- Kahanec, Martin and Zimmermann, Klaus F. (Eds.) (2009a), *EU Labor Markets After Post-Enlargement Migration*. Berlin.

- Kahanec, Martin and Zimmermann Klaus F., (2009b), International Migration, Ethnicity and Economic Inequality, in: Salverda W, Nolan B, Smeeding TM (Eds) *Oxford Handbook on Economic Inequality*. Oxford University Press, Oxford, pp. 455–490.
- Kahanec, Martin and Zimmermann, Klaus F., (2014), How Skilled Immigration May Improve Economic Equality, *IZA Journal of Migration* 3:2.
- Kahanec, Martin and Zimmermann, Klaus F. (Eds.) (2016), *Labor Migration, EU Enlargement, and the Great Recession*. Berlin.
- Kaufmann J. E. and Clayton Donnell, ed. (2004), *Modern European Military Fortifications, 1870-1950: A Selective Annotated Bibliography*, Praeger.
- Kennan, John (2013), Open Borders, *Review of Economic Dynamics* 16:2, L1–L13.
- Kennan, John (2014), Freedom of Movement for Workers, *IZA World of Labor*: 86 doi: 10.15185/izawol.86
- Kollmann, Nancy Shields (2017), *The Russian Empire 1450-1801*, Oxford University Press.
- Kopinski, Dominik and Polus, Andrzej (2019), *Is Botswana Creating a New Gaza Strip? An Analysis of the 'Fence Discourse'*, in : *Crossing African Borders : Migration and Mobility* [en ligne]. Lisboa : Centro de Estudos Internacionais, 2012 (accessed February 4, 2019). <<http://books.openedition.org/cei/235>>. ISBN : 9789898862488.
- Ku, Leighton and Brian Bruen (2013), The Use of Public Assistance Benefits by Citizens and Non-citizen Immigrants in the United States. Cato Institute Working Paper No. 13.
- Langerbein, Helmut (2009), Great Blunders: The Great Wall of China, the Berlin Wall, and the Proposed United States/Mexico Border Fence, *The History Teacher*, Vol 43:1, pp. 9 - 29.
- Lovell, Julia (2006), *The Great Wall: China against the World, 1000 BC – 2000 AD*. New York: Grove Press.
- Massey, Douglas S., Durand, Jorge and Pren, Karen A. (2016), Why Border Enforcement Backfired, *American Journal of Sociology*, 121:5, pp. 1557–1600. doi: 10.1086/684200.
- Massey, Doug. S., and Pren, Karen, A. (2012), Unintended Consequences of US Immigration Policy: Explaining the Post-1965 Surge from Latin America, *Population and Development Review*, Vol. 38:1, pp.1–29. <https://www.ncbi.nlm.nih.gov/pmc/articles/PMC3407978/>
- Miller, Todd (2017), *Storming the Wall: Climate Change, Migration, and Homeland Security*, City Lights Publishers.

- New Scientist. January 27 1990, Hundreds Killed by South Africa Border Fence. <https://www.newscientist.com/article/mg12517011-000-hundreds-killed-by-south-africas-border-fence/> . Accessed February 20, 2019.
- Onishi, Norimitsu, *Eredo Journal; A Wall, a Moat, Behold! A Lost Yoruba Kingdom*. *New York Times*. Sept 20, 1999. <https://www.nytimes.com/1999/09/20/world/eredo-journal-a-wall-a-moat-behold-a-lost-yoruba-kingdom.html>
- Pei, Qing, Lee, Harry F., Zhang, David D. and Fei, Jie (2018), Climate Change, State Capacity and Nomad–agriculturalist Conflicts in Chinese History. Forthcoming: *Quaternary International*. <https://doi.org/10.1016/j.quaint.2018.10.022>
- Peterson, J. E. (2008), *Oman's Insurgencies: The Sultanate's Struggle for Supremacy*. Saqi Books
- Peri, Giovanni (2014), Do Immigrant Workers Depress the Wages of Native Workers, *IZA World of Labor*: 42.
- Pinker, Steven (2011), *The Better Angels of Our Nature: Why Violence Has Declined*. New York, NY: Viking. <http://www.civitas.org.uk/content/files/largescaleimmigration.pdf>
- Pulsiano, Phillip and Wolf, Kirsten, (1993), *Routledge Revivals: Medieval Scandinavia: An Encyclopedia*, pp. 120-121.
- Rigaud, Kanta Kumari; de Sherbinin, Alex; Jones, Bryan; Bergmann, Jonas; Clement, Viviane; Ober, Kayly; Schewe, Jacob; Adamo, Susana; McCusker, Brent; Heuser, Silke; Midgley, Amelia. 2018. *Groundswell : Preparing for Internal Climate Migration*. World Bank, Washington, DC. © World Bank. <https://openknowledge.worldbank.org/handle/10986/29461> License: CC BY 3.0 IGO.
- Rosière, Stéphane and Jones, Reece (2012), Teichopolitics: Re-considering Globalisation Through the Role of Walls and Fences, *Geopolitics*, Vol. 17:1, pp. 217-234.
- Rottman, Gordon L. (2012), *The Berlin Wall and the Intra-German Border 1961-89*. Bloomsbury Publishing.
- Saddiki, Said (2017,). *World of Walls: The Structure, Roles and Effectiveness of Separation Barriers*. Open Book Publisher.
- Spring, Peter (2015), *Great Walls and Linear Barriers*, Pen and Sword Military.
- Stamouli, Nektaria (2016), Inside the Migrant Smuggling Trade: Escapes start at €1000. *Wall Street Journal*. March 29, 2016 <https://www.wsj.com/articles/european-border-crackdown-kick-starts-migrant-smuggling-business-1459260153>
- Torpey, J. (2000), *The Invention of the Passport. Surveillance, Citizenship and the State*. Cambridge University Press.

- Trouwborst, A., Fleurke, F. and Dubrulle, J. (2016), Border Fences and their Impacts on Large Carnivores, Large Herbivores and Biodiversity: An International Wildlife Law Perspective. *RECIEL*, 25: 291–306. doi:10.1111/reel.12169
<http://onlinelibrary.wiley.com/doi/10.1111/reel.12169/full>
- US Customs and Border Protection (2017), U.S. Border Patrol Fiscal Year Southwest Border Sector Deaths (FY 1998 - FY 2017). December 2017. <https://www.cbp.gov/document/stats/us-border-patrol-fiscal-year-southwest-border-sector-deaths-fy-1998-fy-2017>
- US Department of Homeland Security, Office of Immigration Statistics, 2017
https://www.dhs.gov/sites/default/files/publications/17_0914_estimates-of-border-security.pdf
- US Drug Enforcement Administration (2016), National Drug Threat Assessment Summary. 2016
https://www.dea.gov/sites/default/files/2018-07/DIR-001-17_2016_NDTA_Summary.pdf
- Vallet, Élisabeth, ed. (2016), *Borders, Fences and Walls: State of Insecurity?* Routledge.
- Waldron, Arthur (1989), *The Great Wall: From History to Myth*. Cambridge, UK: Cambridge University Press.
- Williams S., Friell J.G.P. (1998), *The Rome That Did Not Fall: The Phoenix of the East*. London: Taylor and Francis.
- Xu, Guoqi (2005), *China and the Great War: China's Pursuit of a New National Identity and Internationalization*. Cambridge University Press.
- Zimmermann, Klaus F.(2014a), Circular Migration. Why Restricting Labor Mobility Can Be Counterproductive., *IZA World of Labor* (2014a): 1 doi: 10.15185/izawol.1.
<https://wol.iza.org/articles/circular-migration/long>
- Zimmermann, Klaus F. (2014b), Migration, Jobs and Integration in Europe, *Migration Policy Practice*, Vol. IV, Number 4, October - November 2014, 4 – 16.
- Zimmermann, Klaus F. (2017a), Migration for Development: From Challenges to Opportunities, GLO Discussion Paper, No. 70, Global Labor Organization (GLO).
- Zimmermann, Klaus F. (2017b), La migration en faveur du développement : des défis aux opportunités, *Revue d'économie du développement*, Vol. 25:1, pp. 13-30.

Appendix Table: Modern Walls and Fences

<i>Builder</i>	<i>Target</i>	<i>Constructed approx.</i>
Dismantled		
East Germany	West Germany	1960s-1989
Hungary	Austria	1960s-1989
Czechoslovakia	West Germany	1960s-1989
Russia/USSR	Finland	1960s-1992
Russia/USSR	Norway	1960s-1992
Before 1990		
Cuba	US (Guantanamo)	1961
Hong Kong	China	1962
Israel	Syria	1973
Cyprus	Cyprus Northern	1974
South Africa	Mozambique	1975
Israel	Lebanon	1976
North Korea	South Korea	1977
Thailand	Malaysia	1978
Morocco	Western Sahara	1980
South Africa	Zimbabwe	1984
India	Pakistan	1988
Between 1990-2001		
United States	Mexico	1993
India	Bangladesh	1994
Israel	Gaza	1994
Kuwait	Iraq	1994
Uzbekistan	Afghanistan	1994
Spain	Morocco-Ceuta	1995
Spain	Morocco-Melilla	1998
Uzbekistan	Kyrgyzstan	1999
Turkmenistan	Uzbekistan	2001
Between 2002-2010		
Israel	West Bank	2002
Botswana	Zimbabwe	2003
Iran	Afghanistan	2003
Saudi Arabia	Yemen	2003
India	Myanmar	2004
Lithuania	Belarus	2004
Brunei	Malaysia	2005
Arab Emirates	Oman	2005
Arab Emirates	Saudi Arabia	2005
Kazakhstan	Uzbekistan	2006
Saudi Arabia	Iraq	2006
Iran	Iraq	2007
Iran	Pakistan	2007
Jordan	Iraq	2008
Jordan	Syria	2008
Russia	Georgia	2008
Egypt	Gaza	2009
Myanmar	Bangladesh	2009
Israel	Egypt	2010
Kazakhstan	Kyrgyzstan	2010
Between 2011-2018		
China	North Korea	2011
Greece	Turkey	2012
Bulgaria	Turkey	2013
Algeria	Morocco	2014
Oman	Yemen	2014
Turkey	Syria	2014
Turkmenistan	Afghanistan	2014
Austria	Slovenia	2015
Azerbaijan	Armenia	2015
Hungary	Croatia	2015

Hungary	Serbia	2015
Kyrgyzstan	Kazakhstan	2015
Kyrgyzstan	Uzbekistan	2015
Latvia	Russia	2015
Macedonia	Greece	2015
Morocco	Algeria	2015
Slovenia	Croatia	2015
Ukraine	Russia	2015
UK	France	2015
Israel	Jordan	2016
Norway	Russia	2016
Tunisia	Libya	2016
Estonia	Russia	2017
Lithuania	Russia	2017
Pakistan	Afghanistan	2017
Turkey	Iran	2017
Iraq	Syria	2018
Planned		
Algeria	Libya	
Hungary	Romania	
India	Bhutan	
Latvia	Belarus	
Malaysia	Brunei	
Malaysia	Indonesia	
Poland	Belarus	
Poland	Ukraine	
Russia	Ukraine	
Turkey	Iraq	